AQUA WORX (Pty) Limited

PO BOX 61151 **BLUEWATER BAY 6212**

CELL 082 411 4846

VAT. REG. 4910262247 CK.2012/100640/07

Email: aquaworx@mweb.co.za

31 PUNTA DEL MAR DE MIST CIRCLE **BLUEWATER BAY 6210**

QUOTATION- Revised

10 March 2021

11x

Re Water filtration plant (30 Kl per 8-10 Hr. Day) Or 3000 L/Hr. plus 25% safety factor.

Based on your water analysis, we would recommend the following plant as per our installation diagram:

1 x Pressure Vessel model 1054 62 Lit. 10 Bar Max. with auto backwash Electronic control valve - 4500 L/Hr max. 3 x bags Glass Filter Media

1 x Pressure Vessel model 1354 104 Lit. 10 Bar Max. with auto backwash Electronic control valve - 4500 L/Hr max. 3 x bags Granulated activated carbon - Virgin Coconut Husk 15 Kg KDF Purifier Medium

Pressure Vessel model 1465 154 Lit. 10 Bar Max. with auto backwash Electronic control valve - 4500 L/Hr. Max. 4 x Bags Granulated Activated Carbon

2 x Water pump Cast Iron 3200 L/Hr at 3.5 Bar or 4700 L/Hr 2bar with Auto Controllers

2 x 5 KI tank diffuser columns

1 x Flocculent Dosing Pump O,5 to 2 L/hr at 10 Bar 1 x Drum 25 Lit. RD 28 Super Floc

1 x Rotameter 40mm with Flow Control Valve

1 x Solenoid Valve 40mm (1 1/4") 220v. N/C

1 x Lot PVC Solvent Weld piping and fittings. 5x5000L Jo 20 touks

Prices exclude VAT

Not included: Water tanks, float switches and float valves, civils or running of electric cables.

CONSULTANT TO THE WATER TREATMENT EQUIPMENT AND PLANT INDUSTRY as below

De-Ionisers

Water Softeners

De-mineralisers

Reverse Osmosis

PH&CD Control systems

Chlorination Dosing Systems

Suppliers of Chlorine Dioxide

Iron Removal Systems

AQUA WORX (Pty) Limited

PO BOX 61151 **BLUEWATER BAY 6212**

CELL 082 411 4846

VAT. REG. 4910262247 CK.2012/100640/07

Email: aquaworx@mweb.co.za

31 PUNTA DEL MAR DE MIST CIRCLE **BLUEWATER BAY 6210**

Plant

QUOTATION

Date 9 May 2021

Re- Stage Two Water Purification RO Plant

Hi Collin

As requested, here is your quote for the add on RO Purification plant.

Required equipment is as follows:

- 1 x RO Self Diagnostic control panel with all necessary instrumentation and Rotameters
- 4 x RO 4040 Brack water membranes,(estimated Permeate production 28 M3 to 31 M3/ Day)
- 4 x RO 4040 Membrane Fibre Wound pressure vessels (300PSI) with end ports
- 1 x RO Membrane mounting panel in Blk 10mm chemical resistant Poly Ethylene
- 1 x RO Multistage Vertically mounted 1,5 Kw 220V. High pressure feed pump
- 1 x RO feed pump Auto controller
- 1 x Water meter 3/4" ports
- 1x dosing pump for Membrane Anti scaling protection
- 10 Liters (2 x 5 Lit. bottles) Brack water anti- scalant concentrate
- 1 x 50 Liter PE. Chemical dosing drum with 200mm screw on lid for anti scalant mixture.
- 1 x Brass PR Valve 3/4" with gauge
- 1 x PTH 20B (Prevention of Total Hardness) Water Improver as quoted for as an option in our quotation of 10 March 2021 with specs.
- 1 x UV 55 S/Steel 55 Watt UV Sterilizer with Ballast. Max. flow = 2400 L/Hr. at 6 Bar with LED warning system. Useful life = 8000 Hrs for lamp.
- 1 x Hydrosphere 40 Lit. with gauge and service valves (Booster Tank with bladder)
- 1 x lot PVC industrial grade solvent weld piping, fittings and valves including pressure testing and calibration of control panel to ensure

satisfactory operation of complete system. New water analysis test certificate in compliance with SABS 241 regulations will also be provided.

CONSULTANT TO THE WATER TREATMENT EQUIPMENT AND PLANT INDUSTRY as below

- De-Ionisers
- De-mineralisers
- Water Softeners

Service of the servic

- Reverse Osmosis
- PH&CD Control systems Damastic O Indication Filtuation

- Chlorination Dosing Systems
- Suppliers of Chlorine Dioxide
- Iron Removal Systems

Flacantation Di